

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. 32 R. 32 <del>W.</del> <sup>W.</sup>	K11 & L13
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ E. _____ S. R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
 FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K11 (Sec. Corner 25, 26, 35, & 36, T43N, R32W):**  
 Spruce post (Not found. See B for subsequent monument)  
 Spruce 4 S69½°W 46 ( " " No subsequent accessories found.)  
 Tam. 8 N45E 43 ( " " " " " " " " )
- Corner L13 (1/4 corner between Sections 1, T42N, R32W & 36, T43N, R32W):**  
 Cedar post (~~not found~~ (Not found. See B for subsequent monuments.)  
 Cedar 4 N53E 7 (Probably found.)  
 Fir 7 N67W 5 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner K11:** On 4/20/76, replaced a 1" I.D. x 63" iron pipe, found as set by unknown persons, with new monument described below. Also found a very old wood post in the swamp moss, but not original. Position is consistent with an original corner 1/2 mile E and other corners around Sec 36. Corner has been used for local surveys.  
**Corner L13:** On 4/19/76, replaced a 1" I.D. x 63" iron pipe, found as set by unknown persons, with new monument described below. Also found a very old rotted cedar post, set at original record bearing and distance from a rotted cedar stump corresponding to a recorded original BT. Corner had been re-witnessed as follows, with nails in blazes facing the corners: Cedar 6 N37°E (mag.) 6.5 ft.; Cedar 6 S17°E (mag.) 8.0 ft.; and Cedar 8 N56°W (mag.) 6.0 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K11:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 White Pine 20 S79°W (mag.) 101.1 ft. "S35, NBT"  
 Dead Tamarack 6 S84°E (mag.) 24.2 ft. "S36, NBT"
- Corner L13:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Cedar 7 N75°W (mag.) 5.2 ft. "1/4S, NBT"  
 Cedar 5 N68°E (mag.) 4.9 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE November 23, 1976

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

