

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. S., R. <u>32</u> E. W.	L 11
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 19, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner between Sections 25 & 36, T43N, R32W:

Hemlock post	(Not found. See B for subsequent monument).
Tamarack 16 S44W 20	(Probably found. No subsequent accessories found)
W. Pine 18 N45E 13	(Probably found. No subsequent accessories found)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Replaced the monument found in place with a new monument described below. The pipe appears to have been set at record bearings and distances from the stumps of probable original BT's, only the W. Pine having any marks remaining, and that only a partial remnant of the lower blaze. Whoever set this pipe, however, reversed the BT's, having set it S44°W 20 lks. from the W. Pine and N45°E 13 lks. from the Tamarack. It was thought best not to correct this defect, as several local surveys have been made from the corner as is, which would thereby be disturbed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3½" aluminum cap
 W. Pine 5 N42°E (mag.) 24.5 ft. "1/4S, NBT"
 Balsam 7 S54°W (mag.) 8.1 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 19, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

