

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>36</u> , T. <u>43</u> N. <del>XX</del> R. <u>32</u> <del>XX</del> W.		<u>7 &amp; 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner 7 (North 1/16 corner between Sections 31 & 36, T43N, R31-32W):  
 Corner 15 (West 1/16 corner between Sections 1 & 36, T42-43N, R32W):  
 Neither corner established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Corner 7: Established 5/2/72 on line between Sec. Cor. 20.051 ch. N and 1/4 cor. 20.051 ch. S.  
 Corner 15: Established 9/23/74 on line between Sec. Cor. 19.993 ch. W and 1/4 cor. 19.993 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Corner 7: 1" I.D. x 36" iron pipe with 4" aluminum cap.  
 Var. 2°23'E Jack Pine 6 S33°W (mag.) 62.5 ft. "1/16S, BT"  
 Jack Pine 5 N 3°E (mag.) 76.3 ft. "1/16S, BT"  
 Corner 15: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Red Pine 4 N12½°W (mag.) 17.8 ft. "1/16S, BT"  
 Black Spruce 6 N67°E (mag.) 18.1 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources  
 13581



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_