

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. XX R. <u>32</u> XX W.	K12 & L12	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	, T. <u>43</u> N. XX R. <u>32</u> XX W.	8	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K12 (1/4 section corner between Sections 35 & 36, T43N, R32W):
 Cedar post (Not found. No subsequent monuments found.)
 Y. Birch 10 S86E 44 (" " " " accessories ")
 Cedar 4 S83W 18 (" " " " " ")

Corner L12 (Center of Section 36, T43N, R32W):
Corner 8 (West 1/16 corner on E & W 1/4 quarter line of Sec. 36, T43N, R32W):
 Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K12: Re-established 9/24/74 on line between Sec. Corners 39.926 ch. to N and to S.
Corner L12: Established 9/20/74 at intersection of quarter-section lines.
Corner 8: Established 9/23/74 on line between Center 1/4 cor. 20.006 ch. E and W 1/4 cor. 20.006 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
Witnesses for Corner K12: Cedar 6 S71°E (mag.) 14.8 ft. "1/4S, NBT"
 Cedar 6 S12°W (mag.) 14.7 ft. "1/4S, NBT"
Witnesses for Corner L12: Cedar 7 N54 1/2°E (mag.) 57.7 ft. "1/4S, BT"
 Cedar 6 N53°W (mag.) 28.2 ft. "1/4S, BT"
Witnesses for Corner 8: White Birch 5 N55°E (mag.) 6.7 ft. "1/16S, BT"
 Black Spruce 4 S3 1/2°W (mag.) 15.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

