

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In.	Corner Code #/
1. Public Land Survey	T 43N R 32W	63
	T R	H3
	T R	
	T R	
2. Property Controlling in Section	S 3 T R	15
	S 4 T R	14
3. Miscellaneous Property In Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on January 27, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

63	H3	15	14
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

63	H3	15	14
Restored by double proportion.	Restored midway on line.	Established midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

63	H3	15	14
Set 1" I.D. 32" I.P. w/4" aluminum cap.	Set 1" I.D. 32" I.P. w/4" aluminum cap.	Set 1" I.D. 32" I.P. w/4" aluminum cap.	Set 1" I.D. 32" I.P. w/4" aluminum cap.
Balsam 8" 850N 28.5' 5/8NBT	Maple 4" N51N 13.3' 1/4s NBT	Cedar 8" 83W 24.9' 1/16s BT	Cedar 7" N25W 8.2' 1/16s BT
Sugar 4" N70W 9.4' 5/8NBT	Maple 6" N25E 11.2' 1/4s NBT	Sugar 4" East 32.8' 1/16s BT	Cedar 5" 838W 26.0' 1/16s BT
Sugar 6" 87&E 28.9' 5/8NBT	Sugar 8" 840E 22.2' 1/4s NBT	Sugar 8" N15E 17.2' 1/16s BT	Balsam 6" 863E 22.0' 1/16s BT

Signed by Keith Sackett Date 2-18-88

Surveyor's Michigan License No. _____

19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

