

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron	Located in:	Corner Code #/
(County)		
1. Public Land Survey	T 43N - R 82W	H1
	T R	12
	T R	13
	T R	
2. Property Controlling in Section	S2 T R	1
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No. . . . ., Recorded Plat . . . . .		
5. Private Claims . . . . .		

Register of Deeds Stamp & File Number

I, **Keith Sackett**, in a field survey on **January 26**, 19**88**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4				3	2				
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H1	12	13	1
Original monument and accessories not found.	Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

H1	12	13	1
Restored midway on line.	Restored by proportion.	Restored by double proportion between corners and land calls.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H1	12	13	1
Set 1" I.D. x 32" I.P. w/4" aluminum cap.	Set 1" I.D. x 32" I.P. w/4" aluminum cap.	12" spruce N88W 12.8' 83 NBT	12" maple S37E 57.3' 1/16s BT
6" birch S32W 11.3' 1/4s NBT	12" ironwood S68W 12.6' 1/4NBT	10" maple S03W 13.4' 510 NBT	10" maple N02W 13.5' 1/16s BT
16" cedar S78E 6.5' 1/4s NBT	8" sugar S26E 17.9' 1/4s NBT	6" maple N77E 11.1' S2 NBT	9" maple S82W 29.5' 1/16s BT
8" cedar N20W 12.7' 1/4s NBT	10" sugar N24E 31.0' 1/4s NBT		

Signed by *Keith Sackett*

Date 2-24-88

Surveyor's Michigan License No. \_\_\_\_\_

19006