

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

County	Located In:	Corner Code #
1. Public Land Survey	T 43N R 32W	F3
	T R	K3
	T R	
	T R	
2. Property Controlling in Section	S 4 T R	16
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No	Recorded Plat	
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **Keith Sackett**, in a field survey on **January 28**, 19 **88** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F3	K3	16
Original monument and accessories not found.	Original monument and accessories not found. Found Wisconsin-Michigan Power Co. monument.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F3	K3	16
Restored midway and on line.	Restored at MI-MI monument.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F3	K3	16
Set 1" I.D. x 32" I.P. w/4" aluminum cap.	Set 1" I.D. x 36" I.P. with plastic cap.	
5" sugar S22N 15.6' 1/4s NBT	12" Balsam S10E 22.7' S12 NBT	7" balsam S70E 36.4' 1/16s BT
5" sugar N83E 12.2' 1/4s NBT	6" spruce N48E 6.7' S1 NBT	5" balsam N09W 12.4' 1/16s BT
5" sugar W10W 32.7' 1/4s NBT	5" spruce N70W 16.6' S2 NBT	8" balsam N82W 19.4' 1/16s BT
		8" aspen S63W 1.0' squared



Signed by Keith Sackett

Date 2/26/88

Surveyor's Michigan License No. 19886