

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

County	Located In	Corner Code //
1 Public Land Survey	T 43N R 32W	62
	T R	
	T R	
	T R	
2 Property Controlling in Section	S 4 T R	7
	S T R	
3 Miscellaneous Property in Sec	S T R	
	S T R	
4 Lot No	Recorded Plat	
5 Private Claims		

Register of Deeds Stamp & File Number

I, **Keith Sackett**, in a field survey on **January 27**, 19 **88**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

B2	7
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

B2	7
Restored by proportion between corners north and south.	Established by proportion between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

B2	7
Set 1" I.D. x 32" I.P. w/4" aluminum cap.	12" cedar N69E 18.7' 1/16" BT with beaver
8" sugar S06E 28.8' 1/4" NBT	4" sugar N09W 4.5' 1/16" BT
7" sugar S47W 21.0' 1/4" NBT	2" sugar S89W 14.4' 1/16" BT
4" sugar N17E 24.7' 1/4" NBT	

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by *Keith Sackett*
 Surveyor's Michigan License No

19006

Date

2-16-88

