

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Iron

(County)	Located In:	Corner Code #/1
1. Public Land Survey	T 43N R 32W	E6
	T 43N R 32W	C6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

C6 June 08, 1994

I, Stephan J. Szyszkowski, in a field survey on 56 March 30, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration.**

{E6} Quarter corner common to Sections 16-17. Corner established in 1849 by Z.B. Searles as follows: Set spruce post, Y. Pine 12 S23E 7, Y. Pine 12 N70W 17. Original line notes show swamp edge calls 5.00 chains south and 3.00 chains north of this corner. Found no subsequent record.

{C6} Quarter corner common to Sections 18-17. Corner established in 1849 by Z.B. Searles as follows: Set spruce post, W. Birch 8 S65E 20, W. Birch 6 N25W 22. Corner shown on surveys by Gary L. Pisoni, PS dated 4-04-92 and 4-07-92, being surveys within Govt Lots 3 & 4. Found no other record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

{E6} Original post and accessories not recovered. Found no evidence of prior monumentation. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a straight line between monumented section corners 2644.76' north and south, being the position proportionate to the original record. From this position, both swamp edge calls noted above check well. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

{C6} Original post and accessories not recovered. Found a 3" dia. cast iron pipe with a spike driven in it's center below the gravel surface of Paint River Road, at the easterly extension of an ancient wire fence line, and in accord with Pisoni's surveys. Distance to monumented corners north and south check fairly well with the original record. Accepted the pipe as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

{E6} Set 1" I.D. pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

21' Double R. Pine N30E 54.2' 1/4S NBT  
 9' R. Pine S46E 32.3' 1/4S NBT  
 11' R. Pine S66W 29.2' 1/4S NBT  
 9' R. Pine N56W 34.6' 1/4S NBT  
 Bearings are magnetic.

{C6} Found spike driven into center of 3" cast iron pipe. chis "+" on top NE cor. transformer housing N84E 32.50' Fd. 1/2" rebar S88E 33.07' 12" Aspen S80E 35.38' Fd. nail in side. 12" Aspen S36E 64.96' Fd. nail in side. 3" choke cherry S86W 25.0' marked 1/4S NBT. Bearings are magnetic. Corner falls 4.5' W. of centerline gravel road.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkowski

Date 6-14-94

Surveyor's Michigan License No 33986