

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)	Located In:	Corner Code #/
1. Public Land Survey	T 43N R 32W	05
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 17 T 43N R 32W	5
	S 17 T 43N R 32W	WC west of 12
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

D5 June 08, 1994

WC May 18, 1994

I, Stephan J. Szyszkoski, in a field survey on 5 May 17, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D5) Quarter corner common to Sections 8-17. Corner established by Z.B. Searles, 1849 as follows: Set cedar post, W. Pine 28 S86W 23, Cedar 18 N15E 11. Survey drawing by Donald Lappala dated 2-24-1980 at Iron County Equalization office show corner monumented by iron pin midway and on a straight line between section corners 2606.72' east and west. Survey recorded by Gary L. Pisoni L.1-P.112 shows iron pin found and used in survey in Section 8. Also survey by Pisoni dated 4-07-92 shows 1/4 corner used to control survey of part of Govt Lots 3 and 4. Found no subsequent record.

(S-Sec. 17) North 1/16 corner Section 17. Corner not established in the original survey. Found no subsequent record.

(WC west of 12) Witness corner between the South 1/16 corner 18/17 and the South 1/16 corner of Sec. 17. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D5) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Recovered the 5/8" iron pin below the surface of Rock Crusher Road and determined it to be 0.3' North and 0.14' East of the proportionate position. Accepted the monument as recovered as being a careful and faithful reestablishment of the corner position. Noted several NBTs marked with upper and lower blazes and measuring nails placed by unknown surveyor.

(S-Sec. 17) Found no monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1318.84' north and Center of Section 1318.84' south. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum WDNR tablet, appropriately stamped.

(WC west of 12) Found no monumentation at this position. Established the corner at a convenient distance east of the Paint River (being 50' east of the edge of the wet tag alder marsh bottomlands) and on a straight line between corners #10 and #12 of Section 17. Corner #12 being a monumented 1/16 corner, and corner #10 being an unmonumented computed position midway between adjacent government corners. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum WDNR tablet, appropriately stamped. From the monument, the monumented south 1/16 corner of Section 17 is 1892.48' east along the 1/16 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D5) Found 5/8" rebar in Rockcrusher road. Made an unmarked upper blaze and set measuring nail in side blaze in:

11" R. Pine N48W 50.20'
 Measured the existing NBTs:

12" J. Pine N86E 23.99'

12" R. Pine S13E 34.26'

14" R. Pine N82W 42.59'

Iron is 2 ft. W'ly of E. edge road.

Bearings are magnetic.

(S) Set 1" I.D. pipe with 4" WDNR cap. Blazed and scribed the following bearing trees:

8" Balsam N46W 12.2' 1/16S BT

2" Maple N73E 31.7' 1/16S BT

5" Maple S66E 26.1' 1/16S BT

5" Maple S73W 20.8' 1/16S BT

Set a 3" squared maple post adjacent.

Bearings are magnetic.

(WC w. of 12) Set 1" I.D. pipe with 4" WDNR cap. Blazed and scribed the following bearing trees:

8" Maple in clump N29W 30.5' WC BT

34" White Pine N66E 58.3' WC BT

24" White Pine S49E 54.4' WC BT

6" B. Ash S54W 14.0' WC BT

Tag alder marsh is 50' West. Bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6-14-94

