

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Iron

	Located In:	Corner Code #/
(County)		
1. Public Land Survey	T 43N R 32W	D6
	T 43N R 32W	E7
	T 43N R 32W	C7
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

C7 June 08, 1994

E7 June 08, 1994

I, Stephan J. Szyszkoski, in a field survey on D6 May 17, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

(D6) Center of Section 17. Corner not established in the original survey. Found no subsequent record.
 (E7) Corner common to Sections 16-17-20-21. Corner established in 1849 by Z.B. Searles as follows: Set cedar post, Tamarack 12 S41W 30, Tamarack 10 N74E 47. Found no subsequent record.
 (C7) Corner common to sections 17-18-19-20. Corner established in 1849 by Z.B. Searles as follows: Set maple post, W. Birch 16 S40W 21, Cedar 10 N24E 29. Original record show distances to adjacent corners: 40.00 north, 80.09 west, 80.00 east, 40.00 south. Found no subsequent record.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D6) Found no monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite quarter corners, all monumented. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (E7) Original post and accessories not recovered. Found a 5" dia. concrete filled stove pipe with a drill rod in the center, projecting 18", in a tag alder swamp. Recovered new bearing trees marked with upper and lower blazes and measuring nails in their sides recently established by unknown surveyor. This monument was probably placed long ago by mining company surveyors. No record of their work was found. Corner checks acceptably with monumented corners to the north and west. Accepted the monument as the best available evidence of the position of the original corner.
 (C7) Original post and accessories not recovered. Found a 1" dia. solid iron bar, previously witnessed by unknown surveyor, with several old blazes facing it. Position of the bar checks fairly well with the original record to monumented corners as follows, 40.045 north, 79.997 west, 40.0 south (from recorded survey by others), and 79.394 east. Accepted the bar as the best available evidence of the position of the original corner.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D6) Set 1" pipe with 4" MDNR cap Blazed and scribed the following bearing trees: 6" Cedar S19W 3.0' 1/4S BT" 20" R. Pine N89W 28.7' 1/4S BT" 20" R. Pine N04W 39.4' 1/4S BT" 20" R. Pine N67E 85.4' 1/4S BT" Placed a 5" squared cedar post adjacent. Corner falls 40' west of center of Rockcrusher road. Bearings are magnetic.	(E7) Found 5" stove pipe, conc. filled with drill rod in center, projecting 18". Measured to the existing NBTs: 12" Tamarack N42W 100.1' 5" Balsam S66E 34.7' 5" Balsam N74E 55.3' Found 5/8" Iron pin with 1.5" dia. iron cap stamped "CF20" on bank of RR grade: N83E 27.85' Bearings are magnetic. Found squared 4" wood post adjacent.	(C7) Found 1" dia. solid iron bar projecting 17". 5" maple w/old blazes, nail and washer, N44E 20.9' 10" Spruce w/old blazes. Set nail and MDNR tag, S14E 20.6' 7" Maple N87W 19.9' marked "S18 NBT" 5" Maple w/old top blaze S20W 13.6' marked "NBT"
---	--	--

Signed by Stephan J. Szyszkoski

Date 6-14-94

Surveyor's Michigan License No. 33986

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

