

**SURVEY & REMONUMENTATION**

**JAN 13 1998**

**SECTION**

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

97 DEC 23 PM 1:29  
L.C. Records L-7 P.152

*Gilbert J. Pisoni*  
REGISTER OF DEEDS

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>R33W</u>	<u>C-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 19, 20, 29, 30, T43N, R33W

I, Gary L. Pisoni, in a field survey on November 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PEER GROUP APPROVED  
*Gary L. Pisoni 12-1-97*  
IRON COUNTY REPRESENTATIVE

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.  
Original Corner; Wood Post

Original Bearing Trees;	Sugar	10"	S50° W	37 lks.(24.42 feet)
	White Pine	16"	N55° E	20 lks.(13.20 feet)

On 3-2-90, Brian R. Taavola, RLS with the Michigan Dept. of Transportation, found a 1" hexagon drill rod laying on ground which was originally set by Herbert F. Larson, Jr. Taavola reset section corner according to a survey map by H.F. Larson dated Feb., 1967. Taavola set a 40" by 3/4" Iron Pipe with a yellow plastic cap. Recorded in Land Corner Certificate L.6, Page 218, on March 23, 1990.

1990 Bearing Trees;	White Pine	12"	S25° E	68.03 feet
	White Pine <th>10"</th> <th>S12° W</th> <th>84.45 feet</th>	10"	S12° W	84.45 feet
	Spruce <th>5"</th> <th>N40°W</th> <th>18.10 feet</th>	5"	N40°W	18.10 feet
	White Pine <th>11"</th> <th>N60° E</th> <th>70.55 feet</th>	11"	N60° E	70.55 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence was recovered.  
Found iron pipe with plastic cap as set by Brian R. Taavola in 1990, accept the iron pipe as the best available evidence for restoring the corner position.

1990 Bearing Trees Recovered:	Balsam	8"	N44° W	18.04 feet
	White Pine <th>15"</th> <th>N55° E</th> <th>70.57 feet</th>	15"	N55° E	70.57 feet
	White Pine <th>13"</th> <th>S23° E</th> <th>67.91 feet</th>	13"	S23° E	67.91 feet
	White Pine <th>13"</th> <th>S14° W</th> <th>84.39 feet</th>	13"	S14° W	84.39 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over top of 3/4" diameter iron pipe set by Taavola, set a 2 inch diameter aluminum pipe monument, 30 inches long, flush with ground surface, with a 3 inch diameter aluminum cap stamped as follows; Iron County Remonumentation, T43N, R33W, S19, S20, S29, S30, 1997, RLS 27457.

Set Steel Sign Post, North, 0.76 feet from monument.

97-47  
Signed by *Gary L. Pisoni*

Date November 29, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971

