

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

- | | | | |
|---------------------------------------|---------------------------|-----|--|
| 1. Public Land Survey | T <u>43N</u> R <u>33W</u> | D-9 | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

REGISTRAR'S OFFICE)
IRON COUNTY, MICH.) SS
RECEIVED FOR RECORD THE 21ST DAY OF
FEBRUARY A.D. 19 95 AT
2:45 O'CLOCK P M. AND RECORDED IN LIBER
6 OF L.C. RECORDS
ON PAGE 379
Mark Wilson
DEPUTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Quarter corner 20, 29, T43N, R33W

I, Gary L. Pisoni, in a field survey on November 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Guy H. Carleton, U.S. Deputy Surveyor in 1851.
Original corner: Wood Post
Original bearing trees:

Hemlock	12"	S 40° E	15 links (9.99 feet)
Hemlock	9"	N 55° W	30 links (19.80 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner located on the North side of a gas pipeline. Corner set by single proportionate measurement and on line between the Northwest and Northeast Section corners of Section 29. Set an aluminum pipe monument 2" above ground surface.
County Record Research on file with County Representative office.

PEER GROUP APPROVED
IRM Gary L. Pisoni
COUNTY REPRESENTATIVE
A.P. 11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R33W, 1/4, S-20, S-29, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Red Maple	11"	N 47° W	43.37 feet
White Pine	13"	N 01° E	44.58 feet
Jack Pine	7"	N 50° E	53.28 feet
Steel Sign Post		S 79° W	0.80 feet



Signed by *Gary L. Pisoni*
Surveyor's Michigan License No. 27457

Date 1-9-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
REVISED JAN., 1975
REVISED JAN., 1983