

SURVEY & REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Iron <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T 43N R 33W	D-11	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

REGISTRAR'S OFFICE)
IRON COUNTY, MICH.) ..SS
RECEIVED FOR RECORD THE 21ST DAY OF
FEBRUARY A.D. 19 95 AT
2:45 O'CLOCK P. M. AND RECORDED IN LIBER
6 OF L.C. RECORDS
ON PAGE 380
Mark Wilson
DEPUTY REGISTRAR OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Quarter Corner 29, 32, T43N, R33W

I, Gary L. Pisoni, in a field survey on November 22, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Guy H. Carleton, U.S Deputy Surveyor in 1851.
Original corner: Wood Post
Original Bearing trees:
White Pine 18" N 59° E 43 links (28.38 feet)
White Pine 20" S 70° W 25 links (16.50 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the stump remains of
the two original bearing trees. A decayed white pine stump which bears S 70° W,
16.50 feet and a white pine stump which bears N 59° E, 28.38 feet from the original
corner location; No remains of the original wood post found.

This corner is accepted as a careful and faithful perpetuation of the position of the
original corner.


County Record Research on file with County Representatives Office.

PEER GROUP APPROVAL
Iron Gary L. Pisoni
COUNTY REPRESENTATIVE
A.P. 11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe
monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation,
T43N, R33W, 1/4, S-29, S-32, 1994, RLS- 27457 from which I established the following
new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Red Maple	7"	N 26° E	28.17 feet
Hemlock	9"	S 29° E	33.84 feet
Hemlock	10"	S 45° W	8.27 feet
White Pine	9"	N 64° W	39.35 feet
Steel Sign Post		East	1.00 feet



Signed by Gary L. Pisoni Date 1-9-95

Surveyor's Michigan License No. 27457