

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>R33W</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:17

L.C. Records: L. 7, P. 274

Robert J. Pisoni

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 9 and 10, T43N, R33W

I, Gary L. Pisoni, in a field survey on Dec. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on Sept. 13, 1851 by Guy H. Carleton, Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:

Hemlock	20"	N 50° W	20 lks (13.20 feet)
Yellow Birch	10"	S 56° E	30 lks (19.80 feet)

PEER GROUP APPROVED
Iron H. Pisoni 12-18-98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found a 4" x 4" concrete monument with 1/2" rebar, 10" above ground surface. Monument set by unknown persons and I accept the above concrete monument as the best available evidence for restoring the corner position.

Distance North and South along Section line are consistent with GLO distance.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set one reference monument, being a 5/8" diameter by 30" long rebar, with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R33W, R.M., 1/4, S-9, S-10, S 17° W, 0.80', 1998, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Red Maple	4"	N 32° W	34.86 feet
Red Maple	7"	N 50° E	24.26 feet
Red Maple	8"	S 04° W	9.31 feet
Red Pine	10"	S 65° W	36.56 feet
R.M.	5/8" x 30" rebar	N 17° E	0.80 feet
Steel sign post		N 17° E	1.60 feet

98-91 Signed by Gary L. Pisoni Date 12-31-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1977
REVISED, MAY 14, 1978
REVISED JAN. 1983
NO. REVISED OCT. 1995
27457



L. 7 P. 274