

**SURVEY &
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>R33W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:17
L.C. Records: L. T. P. 275

Gilbert Pisoni

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 9, 10, 15, and 16, T43N, R33W

I, Gary L. Pisoni, in a field survey on Dec. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in September, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:

Yellow Birch	14"	N 52°W	52 lks (34.32 feet)
Lynn	10"	S 59°E	14 lks (9.24 feet)

On 7/1/74, Arthur O. Enger, RLS with Michigan Dept. of Natural Resources restored the corner position from proportional measurements, and he set a 1" diameter by 36" long iron pipe with a 3 1/2" aluminum cap stamped as follows: DNR, T43N, R33W, S-9, S-10, S-15, S-16, 1974, RLS 13581; 6" above ground surface and recorded in L.C. Certificate, Liber 1, Page 419-420 on 9/17/76.

1974 Bearing Trees:

Sugar Maple	5"	S 71° W	8.7 feet
Sugar Maple	9"	S 09° E	17.9 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found monument as described above and the following bearing trees:

Sugar Maple	13"	S 04°E	18.17 feet
Sugar Maple	8"	S 76°W	8.89 feet

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

PEER GROUP APPROVED
Gary L. Pisoni 12-18-98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the above described corner position, I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	6"	N 25°W	17.45 feet
Sugar Maple	8"	S 58°E	26.01 feet
Steel sign post		N 80°W	0.85 feet

98-94
Signed by *Gary L. Pisoni* Date 12-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 1975
27457 REVISED JAN. 1983
REVISED OCT. 1995



L. T. P. 275