

**SURVEY &  
REMONUMENTATION**

**JAN 19 1999**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>33W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:18  
*L.C. Records: L. 7, P. 277*

*Gilbert Stebbins*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 26, 27, 34, and 35, T43N, R33W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in September, 1851 by Guy H. Carleton, Deputy Surveyor.  
Original Corner; Wood Post  
Original Bearing Trees:

Hemlock	18"	S 70° W	21 lks (13.86 feet)
Yellow Birch	12"	N 70° E	30 lks (19.80 feet)

In June 1985, Charles E. Hein, RLS, found a 1/2" diameter iron pin in the centerline of a county road marking corner position. No bearing trees set. Plat of Survey is recorded in Plats of Certified Surveys, Liber 1, Page 137 on 11/20/90.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a 1/2" diameter iron pin as described above, 2" below road bed surface and located in the centerline of a North/South County road and on line with a fence line to the East.

Distances along Section line to the North and south are consistent with GLO distances.

I accept the above iron pin as the best available evidence for restoring the corner position. Iron pin has been used for various surveys in Sections 27 and 34.

Corner record research on file with County Representative.

PEER GROUP APPROVED  
*Iron A. Pisoni 12-18-98*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a reference monument, being a 5/8" diameter by 30" long rebar, with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R33W, R.M., S-26, S-27, S-34, S-35, S 88° W, 26.98', 1998, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Yellow Birch	11"	N 63° W	51.92 feet
Oak	10"	N 50° E	30.52 feet
R.M.	5/8" x 30" Rebar	N 88° E	26.98 feet
Hemlock	12"	S 48° E	40.90 feet
Steel sign post		N 88° E	27.7 feet

98-104  
Signed by *Gary L. Pisoni* Date *12-21-98*  
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED JAN. 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995



*L. 7 P. 277*