

**SURVEY &
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>R33W</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:24
L.C. Records: L.7, P. 312

Gilbert J. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 26 and 35, T43N, R33W

I, Gary L. Pisoni, in a field survey on December 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11										●			
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in September, 1851 by Guy H. Carleton, Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:

Hemlock	20"	S 50° E	16 lks (10.56 feet)
Hemlock	18"	N 40° W	26 lks (17.16 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Corner restored on line between the Southwest and Southeast Section corners of Section 26 and on a North/South rock fence line, 71.12 feet North of a four-way fence intersection.

Distances along the Section line are consistent with GLO distance.

Corner record research on file with County Representative.

PEER GROUP APPROVED
Iron A. Pisoni 12-18-98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 5/8" x 30" rebar pin in a rock fence line with a 3" diameter aluminum cap over the top of the rebar pin and stamped as follows: Iron County Remonumentation, T43N, R33W, 1/4, S-26, S-35, 1998, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Ironwood	11"	N 03° E	7.04 feet
Sugar Maple	11"	S 71° E	28.05 feet
Sugar Maple	2"	S 23° W	14.14 feet
4 way fence intersection		S 00° 36' 48" E	71.12 feet
Steel sign post		N 03° E	0.82 feet

98-105
Signed by *Gary L. Pisoni* Date 12-31-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1997
REVISED MAY 1975
REVISED JAN 1983
REVISED DEC 1995



L.7 P. 312