

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

	<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey		<u>T 43N R 33W</u>	<u>K-9</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:24

*L.C. Records: L. 7, P. 308*

*Robert Stacie*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 23, 24, 25 and 26, T43N, R33W

I, Gary L. Pisoni, in a field survey on Dec. 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established in September 1851 by Guy H. Carleton, U.S. Deputy Surveyor.  
Original Corner; Wood Post  
Original Bearing Trees:  
Hemlock 14" N 50°W 39 lks (25.74 feet)  
Yellow Birch 12" S 55°E 15 lks (9.90 feet)

In 1989, Gary L. Pisoni, RLS, found an iron bar in concrete lying at the bottom of a hill, monument had been located at the top and edge of a steep hill. I restored the corner position by using the West boundary line of the Supervisor's Plat of New Bristol Location. At the corner position, I set a 5/8" diameter by 30" rebar pin located at the top and edge of a steep hill. No bearing trees set. Original concrete monument was set by local mining company.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original B.T.s found. Found rebar pin as described above and I accept the above rebar pin as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

PEER GROUP APPROVED  
*Iron Co. from 12-18-98*  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

From the above described rebar pin, I set a 3" diameter aluminum cap over the top of the existing rebar pin and stamped as follows: Iron County Remonumentation, T43N, R33W, S-23, S-24, S-25, S-26, 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Spruce	6"	N 22° E	17.77 feet
Spruce	5"	S 83° W	54.11 feet
Popple	8"	N 67° W	77.24 feet
Popple	8"	N 22° W	60.29 feet
Steel sign post		North	0.99 feet

98-99  
Signed by *Gary L. Pisoni* Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN 14, 1983  
REVISED OCT., 1995



*L. 7 P. 308*