

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:31
 L.C. Records L.P. 175
Gilbert J. Pisoni
 REGISTERED DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	K-1
	T <u>43N</u> R <u>33W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section Corner Sections 35,36,T43N,R33W
 Sections 2,1,T42N,R33W

	A	B	C	D	E	F	G	H	I	J	K	L	M
1											●		
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13											●		

I, Gary L. Pisoni, in a field survey on December 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Corner established in 1846 by Austin Burt, U.S. Deputy Surveyor.
 Original Corner: Cedar Post
 Original Bearing Trees:
 Sugar 16" N 61° E 40 lks (26.40 feet)
 Yellow Birch 14" N 18° W 17 lks (11.22 feet)
 In 1851, Guy H. Carleton established the following bearing trees:
 Yellow Birch 14" S 45° E 24 lks (15.84 feet)
 Fir 10" S 25° W 20 lks (13.20 feet)

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
 COUNTY REPRESENTATIVE
 IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No evidence of original B.T.s found.
 Section corner position located in the corner of an old fence line intersection shown to me in 1991 by John Kudwa, property owner, said fence line runs North, South and East. In 1991, I set a 5/8"x30" rebar with plastic survey cap.
 I accept the fence corner as the best available evidence for restoring the Section Corner.
 Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set an Iron County Remonumentation 3" dia. aluminum cap over the top of an existing rebar, said cap is flush with ground surface and stamped as follows: Iron County Remonumentation, T43N, R33W, S35, S36, S2, S1, T42N, 1997, RLS 27457 from which the following bear: (measurement taken to a nail in side of tree)
 Sugar Maple 8" North 19.33 feet
 Sugar Maple 12" N 37° E 45.47 feet
 Red Maple 18" N 80° E 10.20 feet
 Steel sign post S 48° W 0.70 feet

97-5b
 Signed by Gary L. Pisoni Date December 16, 1997
 Surveyor's Michigan License No. 27457

