

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>33W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:18

L.C. Records: L.7 P. 276

Gilbert Stetson

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner Sections 24 and 25, T43N, R33W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in September, 1851 by Guy H. Carleton, Deputy Surveyor.
 Original Corner; Wood Post
 Original Bearing Trees:

Hemlock	10"	S 15° E	24 lks (15.84 feet)
Cedar	9"	N 30° W	53 lks (34.98 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a 1" iron bar encased in concrete and 4" above ground surface.
 Monument was set by local mining company.

Distances East and West to the Section corner are consistent with GLO distances.

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

PEER GROUP APPROVED

Ken A. Pisoni 12-18-98

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a reference monument, being a 5/8" diameter x 30" long rebar, with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R33W, R.M., 1/4, S-24, S-25, N 65° W, 1.10', 1998, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	9"	N 07° E	13.62 feet
Sugar Maple	8"	S 14° E	25.89 feet
Balsam	5"	S 73° W	35.68 feet
R.M.	5/8" x 30" rebar	S 65° E	1.10 feet
Steel sign post		S 65° E	2.0 feet

98-100
 Signed by Gary L. Pisoni
 Surveyor's Michigan License No. 27457

Date 12-21-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995



L.7 P. 276