

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>43N</u> R <u>33W</u>	<u>L-11</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
98 DEC 28 AM 11:18  
*L.C. Records: L. J. P. 278*  
*[Signature]*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 25, and 36, T43N, R33W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established in September, 1851 by Guy H. Carleton, Deputy Surveyor.  
Original Corner; Wood Post  
Original Bearing Trees:  
Ironwood N 45° W 35 lks (23.10 feet)  
Sugar S 55° E 18 lks (11.88 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original B.T.s found. Found a 3/4" diameter iron bar, 8" below road bed surface and located in the North lane of an East/West county road and in line with a rock fence line to the North.

Distances along the East/West Section line are fairly consistent with GLO distances.

I accept the above iron bar as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

PEER GROUP APPROVED  
Iron A. Pisoni 12-18-98  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

From the above described corner position, I set two reference monuments, being 5/8" diameter by 30" long rebar, with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R33W, R.M., 1/4, S-25, S-36, N 40° W, 35.43', 1998, RLS 27457; T43N, R33W, R.M., 1/4, S-25, S-36, N 03° E, 26.00', 1998, RLS 27457 from which the following new reference objects bear:

Utility Pole	N 73°W	73.67 feet
Utility Pole w/transformer	N 74°E	66.38 feet
R.M. 5/8" x 30" rebar	S 40°E	35.43 feet
R.M. 5/8" x 30" rebar	S 03°W	26.00 feet
Steel sign post	S 03°W	26.66 feet

98-107  
Signed by Gary L. Pisoni Date 12-21-98  
Surveyor's Michigan License No. 27457

STATE OF MICHIGAN  
GARY L. PISONI  
LAND SURVEYOR  
No. 27457  
REGISTERED LAND SURVEYOR  
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 14, 1975  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

L. J. P. 278