

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:31
L.C. Records L7 P. 174

Gilbert Stiles
REGISTER OF DEEDS

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>33W</u>	<u>L-1</u>
	T <u>43N</u> R <u>33W</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between Sections 1, T42N, R33W and Sec. 36, T43N, R33W

I, Gary L. Pisoni, in a field survey on December 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established in 1846 by Austin Burt, U.S. Deputy Surveyor
Original Corner: Sugar Post
Original Bearing Trees:

Sugar	10"	N 52° E	54 lks (35.64 feet)
Sugar	10"	N 24° W	46 lks (30.36 feet)

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
COUNTY REPRESENTATIVE
Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original B.T.s found.
Found a 2"x36" light gauge railroad rail at a fence corner which runs East - West and North marking the quarter corner position.
Accept the fence corner and iron rail as the best available evidence for restoring the quarter corner position.
Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set a 2" dia. by 30" long aluminum pipe monument, 3" above ground surface with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R33W, 1/4, S36, S1, T42N, 1997, RLS 27457, from which the following bear: (measurements taken to a nail in side of tree but no signs or scribing)

Utility Pole		N 81° W	77.95 feet
Appletree	11"	N 45° W	15.65 feet
Basswood	8" Multistem	N 02° E	51.18 feet
Cherry	7"	N 55° E	51.04 feet
Steel sign post		S 68° W	0.68 feet

97-4b
Signed by *Gary L. Pisoni* Date December 16, 1997
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

