

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
 (County)

Located In:	Corner Code #
T 43N R 33W	D3
T 43N R 33W	D5
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 25 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3			●									
4	7		8		9		10		11		12	
5			●									
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (D3) Quarter corner common to Sections 5 & 8. 1974: Reestablished by proportionate measurement between Section corners by A.O.Enger. Set 1"IDx32" iron pipe with 3.5" alum. cap. Cedar 5 N07E 24.5', Cedar 6 S38E 58.4'.
 (D5) Quarter corner common to Sections 8-17. 1974: Reestablished by A.O.Enger RLS on line between Section corners 39.994 ch. E and W. Set 1"IDx36" Iron pipe with 3.5" aluminum cap. B.Spruce 6 N85W 6.8', B.Spruce 5 N77E 38.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (D3) Recovered the 1974 monument in good condition and at record bearing and distance from the two cedar NBTs, both in good condition. The position of the corner between the 1973 C3 and the 2003 E3 checks very well with the record (meas. 39.939 ch. West and 39.929 ch. East). Left the monument in place and made new witnesses as described below.
 (D5) Recovered the 1974 monument in good condition, at record bearing and distance from the remains of the 1974 NBTs, both in advanced stages of decay with no markings visible. Checked distances E and W, 39.971 ch. and 39.968 ch., respectively, and found the corner to be on line and in accord with the record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (D3) Found 1"ID I.pipe with 3.5" alum. State of MI cap. Blazed, scribed and set measuring nails in:
 6" Cedar N12E 24.5' to notch *
 8" Cedar S34E 58.4' do *
 10" Cedar S89E 39.95' "1/4S NBT"
 7" Spruce S58W 34.0' do
 * indicates 1974 NBT with scribing visible. Bearings are magnetic. Distances to 2003 NBTs are to nail with plastic tag.
 Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986
 (D5) Found 1"ID iron pipe with 3.5" alum. State of MI cap. Blazed, scribed, and set measuring nails in:
 11" Spruce N80W 30.3' "1/4S NBT"
 5" Spruce N61W 27.6' do
 6" Spruce N02W 38.75' do
 8" Balsam N76E 36.25' do
 Set squared cedar post adjacent. Bearings are magnetic. Distances are to nail with plastic tag.
 Date 4/3/03

