

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 33W 04  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

2. Property Controlling in Section

S 8 T 43N R 33W 11

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 24 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			●		9		10		11		12	
5				●									
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (D4) Center of Section 8. Not established in the original survey. Found no subsequent record.
- (11-Sec. 8) Southwest 1/16 corner, Section 8. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (11-Sec. 8) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The 1/16 corners to the north and east were not monumented in this survey. The 1/16 corner 1318.71' west was established and monumented in 1974, the 1/16 corner (#15) 1324.05' south is a position midway and on a line of mean true bearing between Section and 1/4 corners and not the position of the 1974 monument of record at #15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |           |  |            |
|--|-----------|--|------------|
| (D4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:<br>7" Maple N10E 51.5'<br>6" Maple N76E 56.1'<br>10" Maple South 36.9'<br>10" Maple N65W 87.2'<br>Set squared cedar post adjacent.<br>Bearings are magnetic. Distances are to nail with plastic tag. | "C1/4 8T" | (11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed and set measuring nails in:<br>8" Cedar N51E 34.15'<br>10" Cedar S48E 46.9'<br>8" Cedar S26W 17.5'<br>4" Spruce S89W 15.5'<br>Set squared cedar post adjacent.<br>Bearings are magnetic. Distances are to nails with plastic tag. | "1/16S 8T" |
|--|-----------|--|------------|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/3/2003