

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 in Section

S 8 T 43N R 33W WC N. of 11

3. Miscellaneous
 Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Apr 10 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (WC N. of 11, Sec. 8) Witness corner to the Northeast corner of Government Lot 6, Section 8. Neither were established in the original survey. Found no subsequent record. The NE corner of G.L. 6 is the intersection of the centerline of Chicaugon Creek with the West, N-S 1/16 line of Section 8.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(WC N. of 11). The NE corner of Government Lot 6 falls in Chicaugon Creek and was not monumented. The creek is very broad and confused at this location and it is hard to be certain about the location of the title centerline. Estimated the location of the center of the creek and placed a witness monument on the 1/16 line, 100.00' south of that position. Witnesses below describe the witness corner, 100.00' south of the Government Lot corner. The witness corner is 267.84' north of the SW1/16 corner, Section 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(WC) Set 1"IDx32" I.pipe with 4" alum.
 MDNR cap. Blazed, scribed, and set
 measuring nails in:
 11" Cedar N18W 33.3' "WC BT"
 12" Cedar N55E 27.6' do
 7" Cedar S06E 35.1' do
 24" W.Pine N54W 56.0' do
 Bearings are magnetic. Distances are to
 nail with plastic tag. Set squared
 cedar post adjacent.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/30/03