

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>18</u> T <u>43N</u> R <u>33W</u>	<u>7</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on Jan 31, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 18) North 1/16 corner between Sections 17 and 18. 1974 - Established by A.O. Enger, RLS on line between 1/4 cor. (in pond) 20.039 ch. South and Sec. Cor. 20.039 ch. North. Set 1"IDx36" iron pipe with 3.5" aluminum cap. Sugar Maple 4" N77W 3.3', Sugar Maple 4" N18E 11.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 18) Recovered the 1974 monument in good condition and at record bearing and distance from the Sugar BT NW, in good condition. The Sugar BT NE was not recovered. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Found 1"ID I.pipe with 3.5" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 6" Sugar N77W 3.1' w/old blazes 1974 BT  
 5" Sugar S79E 14.6' mrkd "1/16S BT"  
 7" Sugar S08W 25.0' do  
 7" Sugar S70W 23.7' do  
 Set sq'd post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2/5/08

Surveyor's Michigan License No. 33986