

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	S <u>18</u> T <u>43N</u> R <u>33W</u>	<u>9</u>	
2. Property Controlling in Section	S <u>18</u> T <u>43N</u> R <u>33W</u>	<u>5</u>	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (9-Sec. 18) East 1/16 corner Sec. 18. Not established in the original survey.
- (5-Sec. 18) North 1/16 corner, Section 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9-Sec. 18) Established the corner midway and on a straight line between Center of Section 18 1349.55' west and Quarter corner 1349.55' east. From the corner thus established, a fence corner with wire fences running west and south bears S79E 111.3' distant.
- (5-Sec. 18) Established the corner midway and on a straight line between Center of Section 18 1323.03' south and Quarter corner 1323.03' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" Balsam N83E 25.7' mrkd "1/16S BT"
6" Poplar S12E 13.2' do
5" Balsam S42W 12.3' do
9" Balsam N24W 3.8' do
Set sq'd post adjacent. Bearings are magnetic. | (5) Set 1"IDx48" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
2.5" Tamarack N38E 10.0' mrkd "X X"
4" Tamarack S28E 31.3' "1/16S BT"
2" B.Spruce S14W 29.3' "X X"
2.5" B.Spruce S81W 17.4' "X X"
Set sq'd post adjacent. Bearings are magnetic. |
|--|---|

Signed by Stephan J. Szyszkoski



Date 2/5/08

Surveyor's Michigan License No. 33986