

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>19</u> T <u>43N</u> R <u>33W</u>	<u>5</u>	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Jan 28, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- (5-Sec. 19) North 1/16 corner, Section 19. Not established in the original survey.
  - (6-Sec. 19) Northeast 1/16 corner, Section 19. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (5-Sec. 19) Established the corner midway and on a straight line between Center of Section 19 1323.97' south and Quarter corner 1323.97' north.
  - (6-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |  |   |
|--|---|
| (5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>7" dbl Y.Birch N62E 18.5' mrkd "1/16S BT"<br>7" Sugar S85E 11.0' do<br>8" Sugar S40W 6.15' do<br>8" Sugar N38W 17.1' do<br>Set sq'd post adjacent. Bearings are magnetic. | (6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>4" Sugar N48E 9.2' mrkd "1/16S BT"<br>6" Sugar S34E 12.1' do<br>5" Sugar S25W 16.7' do<br>8" Sugar S86W 18.0' do<br>Set sq'd post adjacent. Bearings are magnetic. |
|--|---|

Signed by Stephan J. Szyszkoski



Surveyor's Michigan License No. 33986

2/5/08