

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>19</u> T <u>43N</u> R <u>33W</u>	<u>9</u>	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	<u>13</u>	
	S ___ T ___ R ___	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Jan 28, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (9-Sec. 19) East 1/16 corner, Section 19. Not established in the original survey.
- (13-Sec. 19) Southeast 1/16 corner, Section 19. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9-Sec. 19) Established the corner midway and on a straight line between Center of Section 19 1340.74' west and Quarter corner 1340.74' east.
- (13-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" Sugar N61E 8.8' mrkd "1/16S BT"
4" Sugar S22E 6.1' do
5" Sugar S29W 11.15' do
10" Sugar N77W 34.65' do
Set sq'd post adjacent. Bearings are magnetic. | (13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
15" Sugar N32E 16.25' mrkd "1/16S BT"
6" Sugar N80E 13.4' do
5" Sugar S04W 14.95' do
5" Sugar S62W 8.7' do
Set sq'd post adjacent. Bearings are magnetic. |
|---|---|



Signed by Stephan J. Szyszkoski

Surveyor's Michigan License No. 33986

2/5/08