

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 ^{N.} XXX , R. 33 ^{XXX} W.	H10
2. PROPERTY CONTROLLING IN SECTION	, T. ^{N.} XXX , R. ^{XXX} W.	
3. MISCELLANEOUS PROPERTY IN SECTION	27, T. 43 ^{N.} XXX , R. 33 ^{XXX} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 30, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


- A. Description of original monument and accessories and/or subsequent restoration:
 Corner H10 (Center of Section 27, T43N, R33W):
 Not established in original survey, but apparently established in early twentieth century: Found a 1" iron pin buried in ground, the top of which is 2 feet below ground level.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner H10: The original iron pin was apparently filled over during road construction activity, the position of the monument having been subsequently marked first with a 1" I.D. x 46" iron pipe and later by a 3/4" solid iron rod driven into the top of the pipe. The iron pin was probably set by Wm. Poyseor or his agents, who owned property on First Fortune Lake in the early years of the century. How it was established is not known, but numerous M/B descriptions in the area were referenced to it over the years.
 Miscellaneous Property Corners: See map on reverse side.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner H10: Plumbed a 1" I.D. x 24" iron pipe with 3 1/2" aluminum cap over the original monument, the top of the new monument being about 6" below ground level.
 Red Pine 24 S63°W (mag.) 65.2 ft.
 Telephone Pole S7 1/2°E 84.0 ft.

Distances are to a nail with 3/4" brass washer stamped "WITNESS MARK"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY Arthur O. Enger DATE May 25, 1978
MICHIGAN REGISTERED LAND SURVEYOR



Arthur O. Enger
 Michigan Department of Natural Resources
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581