

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>XX</u> R. <u>33</u> <u>XX</u> W.	17, J7, K7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner I7 (Section Corner 14, 15, 22, & 23, T43N, R33W):
- Corner J7 (1/4 corner between Sections 14 & 23, T43N, R33W):
- Corner K7 (Section Corner 13, 14, 23, & 24, T43N, R33W):

These corners all occur in county road r/w, and any original evidence has long since been obliterated by road construction. See B, below, for monuments found in place, representing the described corners. Note: Only what was found is being reported here; if these are legal corners it is probably only by common report, as the original field note measurements do not support them.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I7: On 9/15/76, witnessed an unknown length of what appears to be spring leaf, found buried in approx. CL of E-W road at approx. intersection with CL of a woods lane going S (may have once been a township road).

Corner J7: On 8/23/73, witnessed an unknown length of 1" I.D. iron pipe found in approx. construction CL's of intersecting county roads. This pipe bears N89°56.4'E 38.862 ch. from the monument at I7, and S89°32.0'W 40.551 ch. from the monument at K7, the record distances being 40.20ch., respectively.

Corner K7: On 9/15/76, witnessed an unknown length of narrow-gauge railroad track found in place at a right-angled bend in county road. Fence lines to N & E appear to originate from this point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I7: Iron spring leaf, length unknown, buried vertically in road.

1. WMPC Power Pole #76-0950, S61°E (mag.) 54.20 ft. to nail with 3/4" brass washer stamped "WITNESS MARK".
2. ⊕ chiselled in top of a rock, S39°W (mag.) 33.64 ft.

Corner J7: 1" I.D. iron pipe, length unknown, buried in road.

1. Power Pole N64°W (mag.) 35.85 ft.
2. Jack Pine 8 S51°W (mag.) 29.32 ft.

Note: Distances are to a nail with 3/4" brass washer.

Corner K7: Narrow-gauge railroad track iron, length unknown.

1. WMPC Power Pole #76-0952, N60°W (mag.) 36.85 ft.
2. WMPC Power Pole #74-2656, S18°W (mag.) 115.53 ft.

Note: Distances are to a nail with 3/4" brass washer stamped "WITNESS MARK".

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 21, 1976

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

