

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>33</u> , T. <u>43</u> N. S., R. <u>33</u> W.		7a
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 23, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 7a (Most Northerly M.C. between Sections 33 & 34, T43N, R33W):
 Wood post (Not found. Found a 1½" x 40" solid round iron pin)
 Hemlock 10 S67E 14 (" " No subsequent accessories found.)
 Cedar 6 N34E 6 (" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 7a: The iron pin is believed to have been set by Wm. Poyseor, who owned property on Fortune Lake, sometime between 1911 and 1917. Islands in First Fortune Lake were surveyed in 1911, at which time a wood post was reported at this corner by the U.S. surveyor in charge of the survey. A map on file in the Iron County Register of Deeds offices at L. 33, P. 33 of Deeds, dated 1/29/17, shows an iron pin at this corner. The pin found in place appears to be many years old and also appears to agree with the island survey, for which it was the P.O.B. See Book E of Island Surveys in Michigan for details of this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 7a: Replaced iron pin with a 1" I.D. x 36" iron pipe with aluminum cap and a ½" x 12" re-inforcing rod welded to bottom end. The iron pin was re-driven into the ground .42 ft. S of new monument.

White Birch 6 N86°E (mag.) 14.8 ft. "NBT"
 Sugar Maple 4 S1½°E (mag.) 15.8 ft. "NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE March 30, 1976
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

