

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>X.</u> , R. <u>33</u> W. <u>X.</u>	F10
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>43</u> N. <u>X.</u> , R. <u>33</u> W. <u>X.</u>	9
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 30, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner F10 (Center of Section 28, T43N, R33W):**

Not established in original survey. Probably was subsequently established and monumented, but if a monument exists it has been obliterated by highway paving, with no witnesses recorded.

**Corner 9 (East 1/16 corner on E & W 1/4 line of Section 28, T43N, R33W):**

Not established in original survey, but probably was established later. If a monument exists, it has been obliterated by highway re-surfacing and not witnessed.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner F10:** Re-established at intersection of quarter section lines.

**Corner 9:** Re-established on line between Center 1/4 cor. 1338.5 ft. W and E 1/4 corner 1338.5 ft. E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner F10:** 2" PK nail in pavement of US-2

1. White Pine 16 S58 $\frac{1}{2}$ <sup>o</sup>E (mag.) 114.48 ft. to a nail with 3/4" brass washer driven in face of witness blaze.
2. 1" I.D. iron pipe with another 1/2" I.D. iron pipe inside, N20 $\frac{1}{2}$ <sup>o</sup>E (mag.) 63.28 ft.

**Corner 9:** 2" PK nail in pavement of US-2

1. Punch mark in 5-sided bolt head in water line shut-off access pipe, N45<sup>o</sup>E (mag.) 41.67 ft.
2. 1" I.D. x 36" iron pipe with 3 $\frac{1}{2}$ " aluminum cap property boundary marker, S0<sup>o</sup>05'E (true) 80.82 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 27, 1976

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

