

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. XX R. <u>33</u> XX W.	G10
2. PROPERTY CONTROLLING IN SECTION <u>28</u>	T. <u>43</u> N. XX R. <u>33</u> XX W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 30, 19 75, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G10 (1/4 corner between Sections 27 & 28, T43N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 8 S78W 27 (Not found. No subsequent accessories found.)
 Sugar 9 N60E 23 (Not found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 27 & 28, T43N, R33W):
 Not established in original survey. Found an iron pin buried in a former County Road, marking the corner as established sometime after 1920 in a boundary survey at Bewabic Park.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G10: Re-established on line between monuments found at Sec. Cor. 21, 22, 27, & 28 and at S 1/16 corner between Sections 27 & 28, and at a point on this line which is 3 feet South of the S'yly pavement centerline of Highway US-2, its former position according to MDSH&T maps. There probably was once a monument here, but it has been obliterated by repaving of the highway, and was not witnessed.
Corner 14: Replaced the iron pin with a new monument described below. Although no record was found, the iron pin agrees with other m/b and M.C. monuments of record found south of it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G10: 2" PK nail in pavement of US-2.
 MDSH&T concrete r/w marker N1⁰40'W (mag.) 77.89 ft.
 MDSH&T concrete r/w marker S0⁰04.5'W (true) 72.00 ft.

Note: Distances are to a punch mark in center of top of marker.

Corner 14: 9/16" x 12" Copperweld pin with 1" diameter head.
 Hemlock 14 N76⁰W (mag.) 47.92 ft.
 Sugar Maple 20 S39⁰W (mag.) 39.37 ft.

Note: Distances are to head of nail with 3/4" brass washer stamped "WITNESS MARK", driven into root collars of above trees.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 27, 1976

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

