

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. XX R. <u>33</u> XX W.	F9 & G9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner F9 (1/4 corner between Sec. 21 & 28, T43N, R33W):**
 Wood post (Not found. No subsequent monuments found.)
 Sugar 12 S45W 25 (" " " " accessories ")
 Elm 18 N40E 25 (" " " " " ")
- Corner G9 (Section Corner 21, 22, 27, & 28, T43N, R33W):**
 Wood post (Not found. Found 1" x 30" solid round iron bar.)
 Y. Birch 14 N65W 31 (Found four MDSH&T witnesses.)
 Fir 10 S30E 24 (" " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner F9:** Re-established 7/21/75 on line between monuments found at Sec. Cor. 2749.7 ft. W and Sec. Cor. 2682.8 ft. E and on line between an old fence going N and a monument at 1/4 cor. bet. Sec. 28 & 33. This appears to satisfy the section subdivision as evidenced by interior forty boundary fences.
- Corner G9:** On 6/23/75 replaced the iron bar with a new monument described below. The iron bar dates at least to the early 1940's as it is mentioned in MDSH&T highway plan maps. Corner aligns with edge of old field to W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner F9:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Sugar Maple 8 S60°W (mag.) 8.72 ft. "NBT"
 Sugar Maple 5 S46°E (mag.) 3.01 ft. "NBT"
 Note: Distances are to a nail head with 3/4" brass washer stamped "WITNESS MARK" driven into witness blaze.
- Corner G9:** 1" I.D. x 24" iron pipe with 3 1/2" aluminum cap, buried in road.
 Sugar Maple 12 S50°E (mag.) 37.9 ft. "NBT"
 Sugar Maple 6 S39 1/2°W (mag.) 29.5 ft. "NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 27, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581