

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 2. PROPERTY CONTROLLING IN SECTION <u>28</u> | T. <u>43</u> N. XX R. <u>33</u> XX W. | 14a & 16 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 14a (Meander Corner between Sec. 27 & 28, T43N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 Fir 10 N40W 14 (" " " " accessories ")
 - Corner 16 (East 1/16 corner between Sec. 28 & 33, T43N, R33W):
 Not established in original survey. Established sometime after 1920 when a boundary survey of Bewabic State Park was made, and marked with an axle shaft.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 14a: Re-established 7/17/75 on line extended southward from an old monument found at Sec. Cor. 21, 22, 27, & 28 through another old monument found at S 1/16 cor. bet. Sec. 27 & 28 to the shoreline of Fortune Lake. Position agrees with original record and with distances shown on old maps filed in L. 33 of Deeds, P. 33 and P. 201, Iron County Register of Deeds Office, dating back to 1917. The maps show that an iron pin was once set at this corner.
 - Corner 16: On 7/22/75, replaced the axle shaft with new monument described below.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner 14a: 4" aluminum cap in a 5" x 36" re-inforced concrete cylinder.
 Twin Sugar Maple 11 S80°W (mag.) 18.20 ft. "NBT"
 Sugar Maple 4 N 1°W (mag.) 41.40 ft. "NBT"
 - Corner 16: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Sugar Maple 9 N35°E (mag.) 4.66 ft. "1/16S, NBT"
 Red Maple 6 N57°W (mag.) 33.02 ft. "1/16S, NBT"
- Note: Distances to all witness trees are measured direct to the head of a nail with a 3/4" brass washer stamped "WITNESS MARK", driven in face of lower blaze.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 28, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

