

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>28</u>	T. <u>43</u> N. XX S., R. <u>33</u> XX W.	12 & 13
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 12 (South 1/16 corner on N & S 1/4 line of Sec. 28, T43N, R33W):

Not established in original survey nor subsequently, at least not at this position.

Corner 13 (Center of SE 1/4, Sec. 28, T43N, R33W):

Not established in original survey, but apparently approximately established at some subsequent date.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 12: Established 7/22/75 on line between Center 1/4 corner 1308.9 ft. N and S 1/4 corner 1308.9 ft. S. An old field edge and remnant stone fence going W is about 32 ft. S, indicating prior approximate establishment.

Corner 13: Established 7/29/75 at intersection of quarter-quarter lines. Found a 1 1/2" iron pipe N78°13'E 5.48 ft. indicating prior approximate establishment.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 12: 2" PK nail in pavement of road

Sugar Maple 10 N50°E (mag.) 35.03 ft. "BT"

Sugar Maple 10 S32°E (mag.) 42.89 ft. "BT"

Note: Distances are direct to head of tack with 3/4" brass washer stamped "WITNESS MARK" driven into the witness blaze.

Corner 13: 3 1/2" aluminum cap set in a concrete cylinder.

Sugar Maple 6 S55°W (mag.) 6.16 ft. "BT"

Sugar Maple 6 S38°E (mag.) 12.78 ft. "BT"

Note: Distances to nail head driven in witness blaze.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 28, 1976

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

