

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 N. S., R. 33 E. W.	E11 & F11
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E11 (Sec. Cor. 28, 29, 32, & 33, T43N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 12 S76W 19 (" " " " accessories ")
 Sugar 16 N79E 27 (" " " " " ")

Corner F11 (1/4 corner between Sec. 28 & 33, T43N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 8 N13E 25 (" " " " accessories ")
 Sugar 12 S28E 28 (" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E11: On 7/14/75 placed monument described below at an old fence corner of long standing, presumed by common report to be the described section corner.
Corner F11: Re-established 7/21/75 in approx. N & S road centerline, about midway between old fence lines paralleling each side of road about 33 feet distance in each direction, and on W'ly extension of a line between two survey monuments to the east, whose positions are based on this corner. The corner as re-established aligns with an old field edge to W, presumed to be on the section line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E11: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Triple Sugar Maple 6 N40°W (mag.) 6.2 ft. "NBT"
 Sugar Maple 8 S69°W (mag.) 5.8 ft. "NBT"

Corner F11: 9/16"x12" Copperweld pin, top of head flush with road surface.
 Sugar Maple 11 N56°E (mag.) 67.53 ft. "1/4S, NBT"
 Sugar Maple 4 S63°E (mag.) 52.15 ft. "1/4S, NBT"

Note: Distances are to head of nail with 3/4" brass washer stamped "WITNESS MARK", driven in face of lower blaze.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 17, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

