

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>X</u> , R. <u>33</u> W.	E10
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 14, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E10 (1/4 corner between Sections 28 & 29, T43N, R33W):

Wood post	(Not found. No subsequent monuments found.)
Hemlock 10 S25W 46	( " " " " accessories " )
Y. Birch 20 N55E 31	( " " " " " " )

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Corner re-established by re-building Sec. 28 from the evidences of former section subdivision and from MDSH&T highway plan information. Basically, the departure of the corner was determined by extrapolation from interior forty lines of long standing, and the latitude from highway plan data which indicated a corner at a road intersection on Highway US-2, 2 feet north of the centerline of US-2. The position appears to coincide with other fence lines to N and S. There probably was a monument here at one time, but the pavement was re-surfaced and the corner not witnessed beforehand, resulting in its being obliterated. The corner bears N0°28'E 2625.5 ft. from SW corner of Sec. 28 and S1°48.9'E 2649.3 ft. from NW corner of Sec. 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2" PK nail in pavement of US-2.
1. Nail with 3/4" brass washer stamped "WITNESS MARK" on North side of Sugar Maple 16 N63°E (mag.) 111.35 ft.
  2. Center of head of PK nail in NE'ly side of W MPC Power Pole #N72-4081 N43°W (mag.) 86.00 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE November 17, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581