

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>17</u> , T. <u>43</u>	N. _____ S., R. <u>33</u> E. W.	<u>17-13 & 17-14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 17-13 (Center of SE $\frac{1}{4}$, Section 17, T43N, R33W):

Not established in original survey. Found a 1 $\frac{1}{2}$ " I.D. concrete filled iron pipe presumably placed in a position determined by W. E. DeWald in a Govt. Lot 2, Sec. 17 boundary and subdivision survey in the 1940's. Monument believed set by others.

Corner 17-14 (South 1/16 corner between Sections 16 & 17, T43N, R33W):

Not established in original survey. Found a 1" bolt, length unknown, set by persons unknown, apparently proportionately on line between a well point monument at Sec. Cor. 16, 17, 20, & 21 and the South M.C. between Sec. 16 & 17.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 17-13: An explanation of the origin of this corner can be found in Corner Certificate for S 1/16 cor. on N & S 1/4 line of Sec. 17. The true point for the Center of SE $\frac{1}{4}$ is N55 $^{\circ}$ 27.8'W 10.15 feet, as determined by a complete subdivision survey. However, in order not to unsettle m/b lot descriptions in Govt. Lot 2, the corner was accepted as is.

Corner 17-14: The well-point monument at Sec. Cor. 16, 17, 20, & 21 having been discredited (See Corner Certificate for that corner), the true point for this corner is S10 $^{\circ}$ 24.0'E 3.36 ft. from the 1" bolt. As this is such a slight defect, it seemed specious to quibble over it, therefore I report its location as I found it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 17-13: 1" I.D. x 36" iron pipe with 3 $\frac{1}{2}$ " aluminum cap

W. Birch 6 N23 $^{\circ}$ W (mag.) 22.9 ft. "1/16S, BT"

North Corner of Cottage S44 $\frac{1}{2}$ $^{\circ}$ W (mag.) 21.2 ft.

Corner 17-14: 1" Bolt, length unknown

South M.C. 16 & 17 N1 $^{\circ}$ 51.0'E (true) 52.92 ft.

Sec. Cor. 16, 17, 20, & 21 S1 $^{\circ}$ 05.6' W (true) 1325.85 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 17, 1976

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

