

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>8.</u> R. <u>33</u> E. <u>W.</u>	D7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 21, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D7 (1/4 corner between Sections 17 & 20, T43N, R33W):

Wood post	(Not found. See B for subsequent monument.)
Aspen 9 S45W 27	(" " No subsequent accessories found.)
Aspen 10 N40E 19	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Placed a new monument described below at a wood stake guarded by a steel fence post, reportedly set by Earl Davison, former County Road Engineer, in the mid-1930's. It appears to have been set at the end of a random line run from a wood post (also attributed to Davison) at Sec. Cor. 16, 17, 20, & 21, for it is not on the true line between that corner and one a half mile west. It is doubtful if any original evidence was here even in the mid 1930's. The corner as set has been used for a cluster of m/b lot descriptions in Govt. Lot 2, and placing it anywhere else would cause a great deal of unsettling of property lines; therefore I have accepted it as is. (The corner lies South 36.73 ft. from its calculated proportionate position on the line between adjacent section corners.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

Red Pine 5 S47°E (mag.) 9.1 ft. "1/4S, NBT"
 Red Maple 4 S75°W (mag.) 18.6 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 18, 1976

MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

