

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|----------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 2. PROPERTY CONTROL- 17 ING IN SECTION _____ | , T. 43 N. S., R. 33 E. W. | 17-12 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 21, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 17-12 (South 1/16 corner on N & S 1/4 line of Sec. 17, T43N, R33W):

Not established in original survey. Found a tack in a pine slab hub stake guarded by two steel fence posts, reportedly set by W. E. DeWald when he surveyed out some m/b lots in Govt. Lot 2, Sec. 17 in the 1940's.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

It appears that this corner was set by measuring on a compass North bearing 1323.5 feet from a monument at the 1/4 cor. bet. Sec. 17 & 20, then on a compass East (or 90° angle) bearing 1322.6 ft. and setting a point for the center of the SE 1/4, then on a S'ly bearing 1323.4 ft. to a monument previously established for the E 1/16 cor. bet. Sec. 17 & 20, thus establishing lines purporting to be the boundaries of Govt. Lot 2. (How the distances were determined I do not know). Since the North and East quarter-sections were apparently lost prior to 1940, it is unlikely a bona fide section subdivision could be made and I found no evidence of any such subdivision, having to re-establish these missing corners myself before I could make a correct subdivision. That survey determined that the true point for the subject corner is N44° 17.8'W 18.24 ft. from this one. However, not desiring to unsettle the m/b lot boundaries, I accepted DeWald's corner as is.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C. Replaced the tack in pine slab with a 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
- Black Spruce 5 S89°W (mag.) 23.1 ft. "1/16S, BT"
- Black Spruce 8 N83°E (mag.) 22.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 18, 1976

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

