

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. S. R. <u>33</u> E. W.	E 7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 6, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E7 (Section Corner 16, 17, 20, & 21, T43N, R33W):**

Wood post	(Not found. See B for subsequent monuments.)
W. Pine 16 S65W 7	( " " No subsequent accessories found.)
Hemlock 12 N80E 26	( " " " " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Placed a new monument described below at a 4" x 4" x 5' squared cedar post, reportedly set in the mid-1930's by Earl Davison, former County Road Engineer. I do not believe this to be the original U. S. corner position, as it lies in a marsh and the original notes indicate the corner should be on upland. It appears by measurements that it may have been set by measuring in a S'yly direction the record distance from an original M.C. on the S shore of Long Lake bet. Sec. 16 & 17. However, Govt. Lot 3, Sec. 17 has been subdivided into m/b lots and all the descriptions appear to be based on this corner position; therefore I accepted it rather than to unsettle all these descriptions. There is a later monument, a well-point, set by unknown persons N41°14.6'W 21.51 ft. from this one, but with even less evidence to sustain it.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 W. Birch 8 N18½°W (mag.) 57.05 ft. "S17, NBT"  
 W. Birch 5 N80°W (mag.) 66.35 ft. "S16, NBT"

Note: distances are horizontal and to a nail head with brass washer in the witness blaze.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE November 22, 1976

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

