

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>R.</u> R. <u>33</u> EX W.	C4	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>8</u>	T. <u>43</u> N. <u>R.</u> R. <u>33</u> EX W.	3, 3a, & 3b	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C4: Wood post (Not found. No subsequent monuments found.)
 Cedar 8 S9°E 36 (" " " " accessories ")
 Spruce 6 S51W -- (" " " " " ")

Corner 3: Not established in original survey nor subsequently, apparently.

Corners 3a & 3b: Meander corners on N & S sides of Chicaugon Creek. No evidence of original posts or their accessories or of any replacement monuments or accessories.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C4: Re-established 6/19/74 on line between Sec. Cor. 40.121 ch. to N and to S. The distance to Chicaugon Creek is 4.136 ch., although the record distance is 5.657 ch. There seems little doubt as to the probable distance between Sec. Corners on this line, and I am at a loss to explain the discrepancy, unless there was an error in the original measurements, not now demonstrable.
 Corner 3: Established 7/12/74 on line between Sec. Cor. 20.060 ch. N and 1/4 cor. 20.061 ch. S.
 Corner 3a: Re-established 7/12/74 on true sec. line on N bank of Chicaugon Creek, 34.425 ch. S of Sec. Cor. and 5.696 ch. N of 1/4 cor.
 Corner 3b: Re-established 6/19/74 on true sec. line on S bank of Chicaugon Creek 35.925 ch. S of Sec. Cor. and 4.136 ch. N of 1/4 cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for Corners C4, 3, and 3b: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Monument for Corner 3a is a 1" I.D. x 40" iron pipe with 3½" aluminum cap.
 Witnesses for Corner C4: R. Pine 5 N49°W (mag.) 36.7 ft. "1/4S, NBT"
 R. Pine 7 S52°E (mag.) 85.3 ft. "1/4S, NBT"
 Witnesses for Corner 3: Red Maple 2 N20°W (mag.) 9.6 ft. "1/16S, BT"
 Red Maple 2 N27°E (mag.) 9.9 ft. "1/16S, BT"
 Witnesses for Corner 3a: South M. C. is South 1.560 ch.
 J. Pine stub 14 N32°E (mag.) 53.5 ft. "M.C., NBT"
 Witnesses for Corner 3b: R. Pine 16 S18°E (mag.) 69.5 ft. "M.C., NBT"
 W. Birch 14 S15°W (mag.) 84.2 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE October 21, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

