

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> <sup>N.</sup> <del>XX</del> , R. <u>33</u> <sup>XX</sup> <del>W.</del>	<u>A2; A3; &amp; B3</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner A2: Fir post** (Not found. 14" fir N57°W 43 lks. for approx. cor.)
  - Fir 7 S47W 5 (Not found. No subsequent accessories found.)
  - Sugar 12 (Not found. No subsequent accessories found.)
- Corner A3: Cedar post** (Found post point; also a later post point.)
  - Spruce 8 S60E 30 (Not found)
  - Tamarack 14 N76W 7 (Found)
- Corner B3: Wood post** (Not found. No subsequent monuments found.)
  - W. Birch 10 N10E 42 (Not found. No subsequent accessories found.)
  - Aspen 9 S18W 45 " " " " " "

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner A2: Re-established 12/17/73 proportionately on line between Sec. Corners 40.110 ch. S and 39.488 ch. N.**
- Corner A3: Re-monumented 11/6/72 at site of found original post point, confirmed by axe mark traces on rotted tamarack BT stump. Position located by measuring N on a transit line from an original sec. corner 80.213 ch. S. Found old cruisers' tree with blaze facing corner S57°W 25 lks. from corner.**
- Corner B3: Re-established 12/21/73 proportionately on line between Sec. Corners 40.019 ch. E and 40.019 ch. W. Position aligns with old field edge about 10 ch. W, and is about 1 ch. E of top of hill, per original field notes.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner A2: 1" I.D. x 36" iron pipe with 3½" aluminum cap.**
  - Cedar 6 S28°E (mag.) 3.8 ft. "1/4S, NBT"
  - Cedar 7 S31°W (mag.) 26.5 ft. "1/4S, NBT"
- Corner A3: 1" I.D. x 36" iron pipe with 4" aluminum cap.**
  - (Variation 1°20' West) Cedar 14 S18½°W (mag.) 21.4 ft. "S12, NBT"
  - Cedar 10 N70°W (mag.) 43.1 ft. "S1, NBT"
  - Tam. 9 N86°E (mag.) 27.5 ft. "S 6, NBT"
- Corner B3: 1" I.D. x 36" iron pipe with 3½" aluminum cap.**
  - Ironwood 5 N 8°W (mag.) 7.8 ft. "1/4S, NBT"
  - Red Maple 6 S14°W (mag.) 12.3 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE April 17, 1974

MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

