

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 <del>33</del> N. R. 33 <del>33</del> W.	F7 & G7
2. PROPERTY CONTROLLING IN SECTION 16 _____	T. 43 <del>33</del> N. R. 33 <del>33</del> W.	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner F7:** Wood post (Not found. No subsequent monuments found.)  
 Sugar 9 S50W 53 ( " " " " accessories " )  
 Sugar 12 N25E 40 ( " " " " " " )
- Corner G7:** Wood post (Not found. Found 4"x4"x5' cedar post in place.)  
 Cedar 12 N60W 31 ( " " No subsequent accessories found.)  
 Cedar 10 S60E 34 ( " " " " " " )
- Corner 15:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner F7:** Re-established 7/1/74 on line between existing posts 40.143 ch. to E and to W.  
**Corner G7:** On 7/1/74 replaced wood post with monument described below. Found the wood post to be consistent with section corners as accepted 1 mile W and 2 mile E. There are so many inconsistencies with the original record in this township that, lacking any later record, it is hard to say with certainty where many of the corners were placed originally.  
**Corner 15:** Established 7/2/74 on line between Sec. Cor. 20.071 ch. W and 1/4 cor. 20.071 ch. E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
**Witnesses for Corner F7:** Sugar Maple 8 N75°E (mag.) 9.8 ft. "1/4S, NBT"  
 Sugar Maple 7 N37°W (mag.) 5.4 ft. "1/4S, NBT"  
**Witnesses for Corner G7:** W. Spruce 9 N 1/2°E (mag.) 37.4 ft. "S15, NBT"  
 Red Maple 6 S20°E (mag.) 37.3 ft. "S22, NBT"  
**Witnesses for Corner 15:** W. Pine 8 N75°E (mag.) 39.8 ft. "1/16S, BT"  
 W. Pine 7 N82°W (mag.) 34.1 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY Arthur O. Enger DATE October 23, 1975  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

