

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> ^{N.} XX , R. <u>33</u> ^{XX} W.	B5
2. PROPERTY CONTROLL- 18 ING IN SECTION_____	T. <u>43</u> ^{N.} XX , R. <u>33</u> ^{XX} W.	1a & 3
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ ^{N.} _____, R. _____ ^{E.} _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B5: Wood post (Not found. No subsequent monuments found.)
 Cedar 12 S68W 32 (Not found. No subsequent accessories found.)
 Maple 16 N58E 11 (Not found. No subsequent accessories found.)
 Corner 1a: Wood post (Not found. No subsequent monuments found.)
 Spruce 10 S43E 19 (Not found. No subsequent accessories found.)
 Spruce 8 N68E 22 (Not found. No subsequent accessories found.)
 Corner 3: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B5: Re-established 6/18/74 proportionately on line between Sec. Cor. 40.181 ch. W and 39.981 ch. E.
 Corner 1a: Re-established 6/19/74 on true sec. line on E. bank of Chicaugon Creek, 19.255 ch. W of 1/4 cor. and 20.926 ch. E of Sec. Cor.
 Corner 3: Established 6/11/74 on line between Sec. Cor. 20.072 ch. N and 1/4 cor. 20.072 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B5: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 R. Pine 24 S77°W (mag.) 38.8 ft. "1/4S, NBT"
 Red Maple 6 S25°E (mag.) 29.3 ft. "1/4S, NBT"
 Corner 1a: 1" I.D. x 40" iron pipe with 3½" aluminum cap.
 Tamarack 7 S27°E (mag.) 14.2 ft. "M.C., NBT"
 Tamarack 6 N61°E (mag.) 23.7 ft. "M.C., NBT"
 Corner 3: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Cedar 7 S46°W (mag.) 24.0 ft. "1/16S, BT"
 Cedar 5 S66°E (mag.) 27.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE October 29, 1973

CHIEF OF SURVEY PARTY

 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

