

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF:- | LOCATED IN:- | CORNER CODE NUMBER |
|---------------------------------------|---------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 43 N. 33 R. 33 E. W. | B1 |
| 2. PROPERTY CONTROLLING IN SECTION | 6 T. 43 N. 33 R. 33 E. W. | 2 & 2a |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. N. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B1: Hemlock post (Not found. No subsequent monuments found.)
 Hemlock 12 N60E 25 (Found. No subsequent accessories found.)
 W. Pine 24 N75W 33 (Found. " " " ")

Corner 2: Not established in original survey nor subsequently, apparently.

Corner 2a: Wood Meander Post (Not found. No subsequent monuments found.)
 Maple 8 N50W 45 (" " " " accessories ")
 Elm S67W 28 (" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B1: Corner replaced on 10/29/73 from rotted stump of W. Pine BT and rotted remains of down Hemlock BT, the position being further verified by a W. Pine 34 line tree stump which was reported to be 40 links E of the corner. Found all three elements to agree in species, relative and absolute size, distance and bearing; ~~the~~ the corner position is consistent with other original corners to the E.

Corner 2: Established 7/10/74 on line between 1/4 cor. 19.955 ch. W and Sec. Cor. 19.955 ch E.

Corner 2a: Re-established 7/10/74 on true sec. line on W bank of Paint River.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B1: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Cedar 6 S63 1/2°E (mag.) 8.4 ft. "1/4S, NBT"
 Cedar 7 N84°W (mag.) 21.4 ft. "1/4S, NBT"
 Cedar 5 N11°E (mag.) 2.9 ft. "1/4S, NBT"

Corner 2: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Cedar 18 N62°W (mag.) 23.6 ft. "1/16S, BT"
 Cedar 11 S61°W (mag.) 20.4 ft. "1/16S, BT"

Corner 2a: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Silver Maple 9 S 3°E (mag.) 40.2 ft. " M.C., NBT"
 Cedar 18 N62°W (mag.) 35.7 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE September 23, 1975

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

