

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 N. R. 33 E. W.	G 3
2. PROPERTY CONTROLLING IN SECTION _____ 4	T. 43 N. R. 33 E. W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G3: Wood post (Not found. No subsequent monuments found.)
 W. Pine 20 N 5E 49 (Found. No subsequent accessories found.)
 W. Pine 18 S31E 49 (Found. No subsequent accessories found.)

Note: This corner also a Meander Corner.

Corner 14: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G3: Corner replaced from stumps of BT's indicated above, found by measuring from an original corner 1 mile N. Corner falls on bank of river, where an M.C. would likely have been established, and agrees with meander note courses upstream and downstream. Trace of over-growth on stump to NE, but no marks. Stumps agree with record as to species, absolute and relative size, distance, and bearing.

Corner 14: Established 7/8/74 on line between Sec. Cor. 19.940 ch. S and 1/4 cor. 19.940 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G3: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 W. Spruce 8 S42°E (mag.) 6.4 ft. "S10, NBT"
 W. Spruce 13 N47°E (mag.) 23.2 ft. "S 3, NBT"
 Also squared and scribed a 6" balsam S53°W 1.3 ft. (to center).

Corner 14: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 W. Pine 15 N 9°E (mag.) 14.2 ft. "1/16S, BT"
 W. Pine 18 S20°W (mag.) 16.5 ft. "1/16S; BT"


SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE September 23, 1975


 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581